

1. Component NAVY	FY 2026 SPECIAL PROJECTS PROGRAM			2. Date 08 APR 2026
3. Installation(SA) & Location/UIC: M67400 (SH) MARINE CORPS BASE, CAMP SMEDLEY BUTLER (CAMP SCHWAB-6009) HENOKO OKINAWA, JAPAN			4. Project Title Repair Bldg. 3270	
5. Fund Type O&MMC	6. Category Code 21451	7. Project Number BU26PPE74M	8. Project Cost (\$000) 3,529	
9. Cost Estimates				
Item	UM	Quantity	Unit Cost	Cost (\$000)
AUTO ORGANIZATIONAL SHOP CAB FAC#3270 - Repair	SF	25,390	138.99	3,529
B20 - Exterior Doors: roll-up door inspection and repair, 22 EA vehicle bay doors - Construction	LS			(48)
C10 - Interior Construction: wall repair, anchor wire cable resecure, restroom remediation - Construction	LS			(93)
C30 - Interior Finishes: ceiling tile replacement, 2,500 SF mold/mildew damaged - Construction	LS			(38)
D20 - Plumbing: emergency eyewash/shower stations and 2F water cooler RM214 - Construction	LS			(41)
D30 - Mechanical HVAC: ACP replacement, DOAS, exhaust systems, battery room, compressed air - Construction	LS			(1,093)
D50 - Electrical and Communications: lighting 94 fixtures, Cat6 70 drops, TR upgrades, MNS - Construction	LS			(403)
Contingency - 10% of Construction	LS			(172)
Subtotal - Construction				
LSH - Life Safety and Health Allowance, 2.5% of INFADS PRV \$39,507,617 - Construction	LS			(988)
Design - Planning and Design, 6% of Construction Base - Construction	LS			(172)
SIOH - Supervision, Inspection and Overhead, 8% - Construction	LS			(230)
CM - Construction Management, 4% of Construction Base - Construction	LS			(115)
DB Design - Design-Build Design, 4% of Total Funded - Construction	LS			(136)
Subtotal				3,529
Contingency (0.0%)				0
SIOH (0.0%)				0
Total Funded Cost				3,529
Classification of Work Construction				3,529
Special Interest Codes Restoration and Modernization				3,529

1. Component NAVY	FY 2026 SPECIAL PROJECTS PROGRAM			2. Date 08 APR 2026
3. Installation(SA) & Location/UIC: M67400 (SH) MARINE CORPS BASE, CAMP SMEDLEY BUTLER (CAMP SCHWAB-6009) HENOKO OKINAWA, JAPAN			4. Project Title Repair Bldg. 3270	
5. Fund Type O&MMC	6. Category Code 21451	7. Project Number BU26PPE74M	8. Project Cost (\$000) 3,529	
9. Cost Estimates(Continued)				
Item	UM	Quantity	Unit Cost	Cost (\$000)
Total Project Cost				3,529
Planning and Design (0%) (NON ADD)				(0)
10. Description of Proposed Construction:				
The building serves as the primary automotive organizational shop for 4th Marine Regiment (4th MarRegt) and Combat Logistics Battalion 4 (CLB-4) on Camp Schwab. Following completion of this project, the building will remain in operational use for a minimum of 20 years. This project provides for the repair by replacement of the facility's failing mechanical, electrical, and life safety systems, correction of moisture-related architectural deficiencies, modernization of the telecommunications infrastructure, and installation of a mass notification system across both floors to meet current operational requirements, network standards, and UFC compliance. Minor deficiencies identified during the project scope will also be repaired. The project also replaces end-of-life exhaust systems, repairs plumbing safety stations, and addresses exterior door serviceability. MECHANICAL: The project will replace all seven existing HVAC split unit systems and 24 associated indoor fan coil units throughout the facility. New split unit HVAC will be installed in the first and second floor hallways. The air-exchange infrastructure will be redesigned to improve building-wide air circulation, including replacement of ventilation components, evaluation and right-sizing of fan power, and installation of door louvers. All four direct outdoor air supply units serving administrative areas will be replaced. Twenty-two exhaust fans serving restrooms, shops, mechanical rooms, and maintenance bays will be replaced. Ten vehicle exhaust hose reel assemblies in the maintenance bays will be replaced. The abandoned dust collection system in the Wood Shop will be fully removed. The welding exhaust system in the Welding Shop, including fans, roof ventilator, exhaust hood, and associated ductwork, will be repaired and restored. The battery room ventilation and conditioning system will be upgraded to meet code requirements. The compressed air system will be inspected, pressure-tested, and repaired as necessary. ELECTRICAL: All high-bay overhead lighting fixtures will be replaced throughout the facility, including 62 EA standard high-bay fixtures and 30 EA 400-watt metal halide fixtures requiring lift and rigging. All motion sensor-capable and optically-sensored lighting fixtures will be replaced. Electrical panel work, circuit modifications, and branch wiring associated with fixture replacement will be performed on both floors. ARCHITECTURAL: Replace mold/mildew-affected ceiling tile. Repair gypsum and concrete wall damage. Resecure exterior HVAC anchor cables. Remediate restroom mold/mildew. COMMUNICATIONS: New Category 6 infrastructure will be installed throughout the facility according to the current MCIPAC G-6 policy. Both telecom rooms are included in scope. Seventy NIPR network drops will be installed to support 4th Marine Regiment and CLB-4 operational requirements. CYBERSECURITY: The project's design and construction shall fully address Facility-Related Control Systems (FRCS) cybersecurity requirements, to include cybersecurity				

1. Component NAVY	FY 2026 SPECIAL PROJECTS PROGRAM				2. Date 08 APR 2026																
3. Installation(SA) & Location/UIC: M67400 (SH) MARINE CORPS BASE, CAMP SMEDLEY BUTLER (CAMP SCHWAB-6009) HENOKO OKINAWA, JAPAN			4. Project Title Repair Bldg. 3270																		
5. Fund Type O&MMC	6. Category Code 21451	7. Project Number BU26PPE74M	8. Project Cost (\$000) 3,529																		
10. Description of Proposed Construction:(Continued) commissioning. These requirements are in accordance with current Department of Defense (DoD) criteria, Unified Facilities Criteria (UFC) standards, and National Institute of Standards and Technology (NIST) guidelines. Cybersecurity features include hardware, software, documentation, and testing provided by the construction contractor for FRCS. Cybersecurity commissioning covers government-provided documentation and testing for FRCS cybersecurity. PLUMBING: All emergency eyewash and shower stations will be replaced building-wide. Additional emergency shower capability will be added at maintenance bay locations currently served by eyewash only, in compliance with ANSI Z358.1 distance requirements. The second-floor electric water cooler will be replaced. LIFE SAFETY: Emergency lighting fixtures will be replaced with units incorporating integral battery backup throughout the facility. A mass notification system will be installed in compliance with applicable UFC guidelines and Fire Protection Engineering for Facilities.																					
11. Requirement: FACILITY PLANNING DATA: <table style="width: 100%; border-collapse: collapse; margin-top: 10px;"> <thead> <tr> <th style="text-align: left;"><u>Planning Area</u></th> <th style="text-align: left;"><u>CCN</u></th> <th style="text-align: left;"><u>Requirement</u></th> <th style="text-align: left;"><u>UM</u></th> <th style="text-align: left;"><u>Adequate</u></th> <th style="text-align: left;"><u>Substandard</u></th> <th style="text-align: left;"><u>Inadequate</u></th> <th style="text-align: left;"><u>Deficit/ Surplus</u></th> </tr> </thead> <tbody> <tr> <td>SH</td> <td>21451</td> <td>25,390</td> <td>SF</td> <td>25,390</td> <td></td> <td></td> <td></td> </tr> </tbody> </table> PROJECT: Repair deteriorated mechanical, electrical, plumbing, architectural, and telecommunications systems in Building 3270 on Okinawa, Japan to sustain vehicle maintenance operations for 4th MarRegt and CLB-4. (New Mission) REQUIREMENT: Building 3270 is the sole designated automotive organizational shop for 4th MarRegt and CLB-4 on Camp Schwab. Supports all organizational-level vehicle maintenance: maintenance bays, support spaces, and building infrastructure for tactical vehicle readiness. DPRI consolidation relocated CLB-4 from Building 5626, Camp Foster (AC/S G-F Space Reassignment Letter, 27 May 2021; CLB-4 Facilities Acceptance Letter, 28 Jun 2021). Building 3270 is the only available automotive shop for both units on Camp Schwab. CLB-4 fight-tonight posture requires tactical support logistics to be co-located with the supported unit. CURRENT SITUATION: The core operational systems within Building 3270 are experiencing premature and cascading failures that render the facility critically deficient. The root cause is the prolonged exposure to Okinawa's harsh maritime climate, for which the original systems were not adequately specified. Specifically, all seven HVAC systems have reached the end of their service life and can no longer maintain required temperature and humidity levels. This has directly led to widespread mold growth on interior finishes and significant moisture damage to walls. Compounding these issues, the facility is non-compliant with current life-safety mandates; it completely lacks the required Mass Notification System, and its emergency lighting does not have mandated integral battery backups. Furthermore, the building network backbone relies on obsolete Category 5 and Category 3 cabling, which cannot support the bandwidth required for modern command and control or logistics systems. These combined deficiencies compromise personnel health and safety while actively degrading the mission-critical data flow necessary to sustain vehicle readiness.						<u>Planning Area</u>	<u>CCN</u>	<u>Requirement</u>	<u>UM</u>	<u>Adequate</u>	<u>Substandard</u>	<u>Inadequate</u>	<u>Deficit/ Surplus</u>	SH	21451	25,390	SF	25,390			
<u>Planning Area</u>	<u>CCN</u>	<u>Requirement</u>	<u>UM</u>	<u>Adequate</u>	<u>Substandard</u>	<u>Inadequate</u>	<u>Deficit/ Surplus</u>														
SH	21451	25,390	SF	25,390																	

1. Component NAVY	FY 2026 SPECIAL PROJECTS PROGRAM		2. Date 08 APR 2026
3. Installation(SA) & Location/UIC: M67400 (SH) MARINE CORPS BASE, CAMP SMEDLEY BUTLER (CAMP SCHWAB-6009) HENOKO OKINAWA, JAPAN		4. Project Title Repair Bldg. 3270	
5. Fund Type O&MMC	6. Category Code 21451	7. Project Number BU26PPE74M	8. Project Cost (\$000) 3,529

11. Requirement:(Continued)

CURRENT SITUATION:(Continued)

Facility condition: BCI 91 | MDI 17 | HVAC CI 77 | Interior Finishes CI 82 | Exterior Enclosure CI 84

FLOODPLAIN: Not sited in floodplain per Okinawa Hazards Map (OUSD memo, 11 Feb 2014).

IMPACT IF NOT PROVIDED:

Failure to execute this project will create unacceptable health and life-safety risks while halting the essential maintenance management functions that enable vehicle readiness for both the 4th Marine Regiment and CLB-4. The inevitable failure of the end-of-life HVAC systems will render the administrative spaces uninhabitable, preventing personnel from managing work orders, ordering parts, and conducting readiness reporting. This effectively paralyzes the entire maintenance workflow of this sole-source facility. Furthermore, the uncontrolled humidity will worsen the spread of mold, posing a direct health hazard to personnel. Critically, the absence of a compliant Mass Notification System and reliable emergency lighting creates an unmitigated life-safety risk, leaving personnel without a reliable means of alert or safe egress during an emergency. This is compounded by the antiquated telecommunications infrastructure, which cannot support the data flow required for modern logistics and command and control systems. In summary, while mechanics may physically access the maintenance bays, the inability to use the administrative support spaces will functionally cripple the entire operational output, directly degrading vehicle readiness for two forward-deployed units.

NOTES:

Status of Design: Preliminary Planning

Preliminary Planning. No design contract has been awarded. Delivery is Design-Build (DB) to FEAD.

Based on the criteria established in MCO P11000.5G w/CH-1 & CH-2, a formal Economic Analysis (EA) is not required for the renovation of Building 3270. The estimated Total Project Cost of \$3,528,000 falls below the \$5,000,000 NPV EA threshold, and the repair scope constitutes 8.9% of the facility's Plant Replacement Value (PRV) of \$39,507,617, which is well below the 75 percent limit.

25,390 SF, two-story permanent facility, placed in service 04 Jun 2013. G0J-owned (FMRA INGRANT ID 1277). No major repair since initial construction.

Building 3270 serves as designated automotive shop during DPRI-directed interim consolidation on Camp Schwab. Original Camp Kinser relocation plan revised; both units remain at Camp Schwab pending future realignment. Upon relocation, buildings return to base inventory. Repair investment is justified by current operational requirement and remaining service life regardless of long-term basing disposition.

iNFADS record (RPUID 1174058, Facility ID NFA200001061770) reflects 4th MarRegt (M13201) only; CLB-4 (M29030) utilization deleted during Mar 2024 Asset Evaluation. Formal space reassignment (27 May 2021) and CLB-4 acceptance (28 Jun 2021) document 11,720 SF occupancy for AUTO ORG SHOP. iNFADS update pending through RPA0.

Note: The PRV in the current text (\$45,526,139) does not match our iNFADS-confirmed PRV (\$39,507,617). Use \$39,507,617 - that is the confirmed RPUID 1174058 value.

Other Non-Project Costs (If applicable):

The following related projects support the consolidation of 4th Marine Regiment and Combat Logistics Battalion 4 on Camp Schwab under the DPRI program of record (Post G-F Decision, Camp Schwab Projects): BU26PPE70M (PAX 387356), SCH-1024, Expand

1. Component NAVY	FY 2026 SPECIAL PROJECTS PROGRAM				2. Date 08 APR 2026
3. Installation(SA) & Location/UIC: M67400 (SH) MARINE CORPS BASE, CAMP SMEDLEY BUTLER (CAMP SCHWAB-6009) HENOKO OKINAWA, JAPAN			4. Project Title Repair Bldg. 3270		
5. Fund Type O&MMC	6. Category Code 21451	7. Project Number BU26PPE74M	8. Project Cost (\$000) 3,529		

11. Requirement:(Continued)

NOTES:(Continued)

Armory/Convert Gym to Admin and OSS Vault; BU26PPE71M (PAX 387433), SCH- 3314, Convert to 4th Marine Regiment HQ/UDP West; BU26PPE72M (PAX 387624), SCH-3213, Convert to CLB-4 HQ; BU26PPE73M (PAX 387622), SCH- 3237, Re-partition Warehouse for Three Units/Telecomm Room with Fire Suppression Design.

Sources of equipment associated with this project from other appropriations are:
NONE.

Phasing and Timeline for inter-related projects (if applicable)
N/A

ADDITIONAL:

A. Facilities Data:

Fac No	Facility ID	Facility Name	CCN	UM	Quantity	PRV(\$000)	MDI	MTD	CONF	COND	Built	MUIC	SC
3270	NFA200001061770	AUTO ORGANIZATIONAL SHOP CAB											
	21451 SF	25,390	46,723	17	MS	100	91	06-04-2013	M67400	00			

B. Hazardous Material Information:
N/A

C. Economic Analysis:
Economic Analysis required per OPNAVINST 11010.20J ☐ (Yes if Checked)
Economic Alternatives Considered:

(1) Status Quo:
[Not-Viable]:

The status quo alternative is continuation of the current building configuration without repair. Under this alternative, all seven end-of-life HVAC systems would remain in service, the facility would continue to operate without a compliant Mass Notification System, emergency lighting would remain without mandated integral battery backup, and the network backbone would remain on obsolete Category 5 and Category 3 cabling. This alternative is not viable. The ongoing HVAC failures are actively causing mold growth and moisture damage, creating direct health hazards for personnel. The absence of a compliant Mass Notification System and reliable emergency lighting constitutes an unmitigated life-safety violation. The antiquated telecommunications infrastructure cannot support the data requirements of modern logistics and command and control systems. Continued deferral guarantees further system degradation and increasing risk of a complete operational shutdown. This alternative does not meet the mission requirement and was not carried forward.

(2) Sustainment/Maintenance:
[Not-Viable]:

The sustainment and maintenance alternative would address only routine upkeep and preventive maintenance of existing systems without replacing the end-of-life HVAC equipment, modernizing the telecommunications infrastructure, or installing the required life-safety systems. Targeted maintenance of the failing HVAC units is no longer cost-effective given their age and condition and would not resolve the root cause of the moisture and mold deficiencies. Routine maintenance has no mechanism to install a Mass Notification System, upgrade emergency lighting to meet current UFC mandates, or replace the obsolete cabling backbone. This alternative does not meet the mission requirement and was not carried forward.

1. Component NAVY	FY 2026 SPECIAL PROJECTS PROGRAM		2. Date 08 APR 2026
3. Installation(SA) & Location/UIC: M67400 (SH) MARINE CORPS BASE, CAMP SMEDLEY BUTLER (CAMP SCHWAB-6009) HENOKO OKINAWA, JAPAN		4. Project Title Repair Bldg. 3270	
5. Fund Type O&MMC	6. Category Code 21451	7. Project Number BU26PPE74M	8. Project Cost (\$000) 3,529

11. Requirement:(Continued)

ADDITIONAL:(Continued)

- (3) Restoration/Modernization:
[Viable Project]:

The restoration and modernization alternative provides for the repair by replacement of all seven end-of-life HVAC split unit systems, the redesign of air-exchange infrastructure to improve building-wide air circulation, the replacement of all high-bay and motion sensor-capable lighting fixtures, the remediation of mold and moisture-affected finishes, the complete removal of all existing Category 5 and Category 3 cabling and installation of new Category 6 infrastructure throughout both floors in compliance with current MCIPAC G-6 policy, the installation of a compliant Mass Notification System, the replacement of all emergency lighting with units incorporating integral battery backup, and the implementation of FRCS cybersecurity requirements per applicable UFC and NIST guidelines. This is the only alternative capable of restoring Building 3270 to a safe, habitable, and operationally functional condition for a projected minimum service life of 20 years. This alternative is the recommended course of action and is identified as the Minimum Viable Project in the Analysis Results section.

- (4) Lease:
[Not-Viable]:

The lease alternative would involve identifying and leasing off-installation commercial or government-owned space to provide automotive organizational maintenance capability for both units. This alternative is not viable. The operational requirement for on-installation vehicle maintenance directly supporting the tactical readiness of forward-deployed forces on Camp Schwab cannot be met by commercial off-installation facilities. Building 3270 is the only available automotive shop for both units on Camp Schwab, and the CLB-4 fight-tonight posture requires tactical support logistics to be co-located with the supported unit. This alternative does not meet the mission requirement and was not carried forward.

- (5) New Footprint:
[Not-Viable]:

The new footprint alternative would involve constructing a new, purpose-built automotive maintenance facility on Camp Schwab. This alternative is not viable. Building 3270 has been designated as the primary automotive organizational shop under the DPRI-directed interim consolidation plan for Camp Schwab. New construction on this installation is constrained by available land, host-nation land use agreements, and the GOJ-owned status of existing infrastructure under the FMRA program. A new footprint would require significantly greater investment, a longer delivery timeline, and additional programming actions not supportable within the current program of record. The existing building's systems are repairable and the facility is otherwise structurally sound. This alternative does not meet cost-effectiveness criteria and was not carried forward.

1. Component NAVY	FY 2026 SPECIAL PROJECTS PROGRAM		2. Date 08 APR 2026
3. Installation(SA) & Location/UIC: M67400 (SH) MARINE CORPS BASE, CAMP SMEDLEY BUTLER (CAMP SCHWAB-6009) HENOKO OKINAWA, JAPAN		4. Project Title Repair Bldg. 3270	
5. Fund Type O&MMC	6. Category Code 21451	7. Project Number BU26PPE74M	8. Project Cost (\$000) 3,529

11. Requirement:(Continued)

ADDITIONAL:(Continued)

(6) Analysis Results:

Five alternatives were considered to address the mission requirement. The status quo, sustainment and maintenance, lease, and new footprint alternatives were each evaluated and not carried forward. The occupying units must vacate their current facilities and be resident in Building 3270 no later than the third quarter of FY 2028. That deadline is driven by the DPRI-directed FRF demolition sequence at Camp Schwab, which requires existing unit facilities to be cleared to make way for decades of follow-on construction including a new runway, aircraft apron, and supporting infrastructure. The demolition line does not flex around unit availability. Status quo and sustainment-only alternatives do not produce a habitable, code-compliant facility capable of supporting the required mission functions. Leasing is not a viable path for classified operational and storage space on a Marine Corps installation in Okinawa. New construction cannot be programmed, designed, and delivered within the available window. The restoration and modernization of Building 3270 is the only alternative that satisfies the mission requirement, complies with applicable UFC, physical security, and life-safety standards, and can be executed within a schedule consistent with the Q3 FY 2028 occupancy requirement.

MINIMUM VIABLE PROJECT (MVP): The restoration and modernization of Building 3270, as scoped, is the minimum viable project. Every scope element included represents the minimum work necessary to establish compliant operations and support functions for the occupying units, restore the building systems required for sustained habitation, and meet applicable code and physical security requirements within the mandated timeframe. No scope element has been included beyond what is operationally required or technically necessary to deliver a code-compliant, enduring solution by the required occupancy date.

D. Phasing (\$000): NONE

E. Other Proposed Projects:

The following related projects support the consolidation of 4th Marine Regiment and Combat Logistics Battalion 4 on Camp Schwab under the DPRI program of record (Post G-F Decision, Camp Schwab Projects): BU26-101M (PAX 387356), SCH-1024, Expand Armory/Convert Gym to Admin and OSS Vault, \$10,325,000; BU26-102M (PAX 387433), SCH-3314, Convert to 4th Marine Regiment HQ/UDP West, \$2,100,000; BU26-5865M (PAX 387624), SCH-3213, Convert to CLB-4 HQ, \$1,680,000; BU26-5836 (PAX 387622), SCH-3237, Re-partition Warehouse for Three Units/Telecomm Room with Fire Suppression Design, \$692,000. Total related program cost: \$17,019,000.

F. Status of Design: Preliminary Planning

Preliminary Planning. No design contract has been awarded. Delivery is Design-Build (DB) to FEAD

G. Equipment associated with this project which will be provided from other appropriations: NONE

Activity POC: MCBB Planning

Phone No: 315-645-5470

Attachments:

Site Plan

Detailed Cost Estimate

NEPA Documents

BFR (Basic Facility Requirement)

Other

1. Component NAVY	FY 2026 SPECIAL PROJECTS PROGRAM			2. Date 08 APR 2026									
3. Installation(SA) & Location/UIC: M67400 (SH) MARINE CORPS BASE, CAMP SMEDLEY BUTLER (CAMP SCHWAB-6009) HENOKO OKINAWA, JAPAN			4. Project Title Repair Bldg. 3270										
5. Fund Type O&MMC	6. Category Code 21451	7. Project Number BU26PPE74M	8. Project Cost (\$000) 3,529										
12. Signatures: <table border="0"> <thead> <tr> <th><u>Position</u></th> <th><u>Electronic Signature</u></th> <th><u>Date</u></th> </tr> </thead> <tbody> <tr> <td>Public Works Officer</td> <td>Justus OConnor</td> <td>21-Apr-2026</td> </tr> <tr> <td>Branch Chief</td> <td>Bil Hawkins</td> <td>10-Apr-2026</td> </tr> </tbody> </table>					<u>Position</u>	<u>Electronic Signature</u>	<u>Date</u>	Public Works Officer	Justus OConnor	21-Apr-2026	Branch Chief	Bil Hawkins	10-Apr-2026
<u>Position</u>	<u>Electronic Signature</u>	<u>Date</u>											
Public Works Officer	Justus OConnor	21-Apr-2026											
Branch Chief	Bil Hawkins	10-Apr-2026											